# BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/06/2020-21 Date: 20.08.2020

Indet No: BBMP/2020-21/RD/WORK_INDENT44411

SCHEDULE -B

Name of Work: Comprehensive development of drains left side of muthyalamma temple in ward no 17 J P park

| Sl.No | Qty | Description of work | Unit | In Figures (Rs.) | In Words (Rs.) |
|---|---|---|---|---|---|
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | 723.60 | Removing & Refixing stone slabs of drains and pointing in C.M (1:3) | Sqm | 116.00 | Rupees One Hundred Sixteen Only |
| 2 | 331.50 | Earthwork in surface excavation for levelling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications. | Cum | 276.00 | Rupees Two Hundred Seventy Six Only |
| 3 | 108.54 | Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. | Cum | 5881.00 | Rupees Five Thousand Eight Hundred Eighty One Only |
| 4 | 964.80 | Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm | Sqm | 1066.00 | Rupees One Thousand Sixty Six Only |
| 5 | 482.40 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. - do - 10 cms thick | Cum | 1010.00 | Rupees One Thousand Ten Only |
| 6 | 2572.80 | Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded) | Rmtr | 64.00 | Rupees Sixty Four Only |
| 7 | 1206.00 | Providing one line dressing to granite stone slab / granite stone masonry as per specifications. | Sqm | 994.00 | Rupees Nine Hundred Ninety Four Only |

Signature of the contractor



Executive Engineer
RRNagara Division
BBMP

| | | | | | |
|---|---|---|---|---|---|
| 8 | 108.00 | Providing and Fixing RCC pre cast covering Slab of 250 mm thick for drain in cement concrete M20 using graded granite jelly 20 mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc., complete and as per drawing and the directions of Engineer in-charge. (Data Rate) | Sqm | 6060.00 | Rupees Six Thousand Sixty Only |
| 9 | 235.00 | Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per pecifications. | Cum | 103.00 | Rupees One Hundred Three Only |

Signature of the contractor



Executive Engineer
RRNagara Division
BBMP